



**LAKE & LAND**

CIVIL CONSTRUCTION & EARTH ENGINEERING

# JACKSONS GULLY CULVERT GOLDEN POINT ROAD BLACKWOOD, VICTORIA



## PROJECT OVERVIEW

DESIGN AND CONSTRUCT, MAJOR CULVERT,  
GOLDEN POINT ROAD, TOWNSHIP OF BLACKWOOD

**CLIENT:** THE MOORABOOL SHIRE

# THIS PROJECT RECENTLY WON THE CIVIL CONTRACTORS FEDERATION '2013 EARTH AWARD'

## LAKE & LAND PTY LTD

### JACKSONS GULLY CULVERT, GOLDEN POINT ROAD, BLACKWOOD, VICTORIA

#### TASK

- Replace existing Corrugated Iron Culvert with concrete culvert

#### OBJECTIVES

- Maximise flow under roadway
- Minimise Vegetation removal,
- Minimise Traffic Disruption,
- Minimise sedimentation transport
- Build a fish Ladder
- NO Harm to anyone
- Use the existing Corrugated steel pipe as a sleeve for the concrete pipe
- Realignment of the entrance of the culvert to encourage flow
- NO vegetation removal
- Constructed innovative fish ladder using mussel Spat Rope

#### PROJECT MANAGEMENT

##### PROJECT PLANNING AND MANAGEMENT

- Lake & Land Pty Ltd - Construction
- Alex Brunacci - Design Concept/ Project Management
- Tim Hamilton – Structural Design
- StQuintin Consulting – Proof checking
- Driscoll Engineering – Superintendent for Moorabool Shire Council
- Melbourne Water - Approval Authority
- DSE – Vegetation Authority
- Cost \$240K.
- Awarded August 2012
- Concept Design September 2012
- Works Approval October 2012
- Works Commenced November 2012
- Completed December 2012

#### ENVIRONMENTAL AND SOCIAL MANAGEMENT

##### MANAGEMENT OF ENVIRONMENTAL CONSTRAINTS AND ENHANCEMENT

- Project specific environmental management systems and plans.
- Development of a Site Specific Environmental management plan.
- Successful implementation and completion of project within nominated environmental guidelines.
- No trees removed or trimmed to undertake works.
- Use precast concrete where possible so as to minimise placement of concrete in waterway

- Reuse all excavated materials.
- Monitor environmental systems by Melbourne water.

#### TECHNICAL COMPLEXITY

##### TECHNICAL AND COMPLEX ASPECTS OF THE PROJECT.

- Trenchless Excavation
- Self-levelling pressure Grouts
- HDPE Skids
- Natural Rock construction of Fish ladders in waterways
- Use of mussel spat rope

#### ACHIEVING TIMING AND BUDGET TARGETS

- Original plan was to be completed all civil works by December 2012.
- Project approval application made to Melbourne water October 2nd 2012
- Conditional approval received from Melbourne water on 21st November 2012.
- Conditions on the permit to be fulfilled did not enable us to commence until after 4th December 2012.
- Pipes were installed early December precast pit and headwalls mid-December.

